

# FACT SHEET

## PARK ROAD 22 BRIDGE

FROM WHITECAP BOULEVARD TO SH 361 (COMMODORES DRIVE)  
Nueces County, Texas

Total Length: 3,000 ft.

Type: New Bridge

Sponsor: City of Corpus Christi

Right-of-Way Needed: None

Construction Duration: 12 months

## Location



## Project Elements

- Construct two bridges (northbound and southbound) over a proposed canal within the existing TxDOT-owned Park Road (PR) 22 right-of-way.
- PR 22 vertical profile will be raised approx. 12 feet to span the proposed canal for boat/pedestrian traffic.
- Inside shoulders will be widened to 10 feet.
- Proposed bridges will include three precast concrete arch spans (center span 46 feet wide will cross canal; two spans 36 feet on either side of the 46 foot span).
- Boardwalk for pedestrians will cross under the roadway.
- Approx. 42-foot wide canal will include articulated concrete matting to prevent erosion. Sheet pile retaining walls will be employed. Support structures under the water line will be armored.
- During construction, traffic will be diverted to one side while the other side is being constructed with construction anticipated to begin on northbound lanes first.
- Residential and business access will be maintained throughout construction.



# AGENDA

**PUBLIC HEARING  
THURSDAY, APRIL 7, 2016**

## **PARK ROAD 22 BRIDGE**

**FROM WHITECAP BOULEVARD TO SH 361 (COMMODORES DRIVE)**

**Nueces County, Texas**

**6:00 pm      Display Viewing / Open House**

**7:00 pm      Formal Hearing**

**- Welcome/Introduction**

**- Technical Presentation**

**- 15-Minute Recess**

**- Public Comment Session**

**- Adjourn**